



## MSINGA MUNICIPALITY

QUOTATION NO: QU00004/2020/2021/COR

### INVITATION OF QUOTATION ABOVE R 30 000 TO R 200 000.

Quotations are hereby invited in terms of section 18(a) of the Msinga Municipality's Supply Chain Management Policy together with section 83 of the Municipal Systems Act, No.32 of 2000, as amended and read together with sections 110,111 and 112 of the Municipal Finance Management Act No.56 of 2003 for: **REFURBISHMENT OF THUSONG CENTER**

QUANTITY	DESCRIPTION
01	<b>Refurbishment of Thusong Centre offices and Renovation of wood house for front service</b>
	<b>Specification attached</b>

The Closing date is 19/04/2021 at 12h00. No late quotations will be considered and Msinga Municipality does not bind itself to accept the lowest of any quotations and reserves the right to accept the whole or any part of the quotation. All quotation must be submitted on sealed envelope and be dropped in the tender box in reception.

### NOTICE TO ALL BIDDERS

1. Failure to submit the following documents the tender will be non-responsive:


- Tax Clearance Certificate/Pin number
- CSD
- Company registration documents
- Company municipal rates, electricity or water account not older than 3 Months, proof of Residential lease of rental or sworn affidavit if the business operates at a place of rural residence.
- MBD 1 form of tax compliance
- MBD 3.1 Pricing Schedule – Firm Prices
- MBD 4 form of declaration of interest
- MBD 6.1 Preference points claim form
- MBD 6.2 Declaration certificate for local production and content
- MBD 8 Declaration of Bidder's Past Supply Chain Management Practices.
- MBD 9 form of certificate of independent bid determination

2. BBB EE Certificate (**COPY MUST BE CERTIFIED**)/ letter from Auditors in case of EMEs for only points, must be a certified copy.

Quotation will be evaluated in terms of the Council Supply Chain Management Policy on the 80/20 Preferential Point System for regulation 2017.

Price(s) must be valid for at least ninety (90) days from date of your offer.

NB: No Quotations will be considered from persons in the service of the state.



\_\_\_\_\_  
**Mr. SL Sokhela**  
**Municipal Manager**

12/04/2021  
**Date**

## SPECIFICATIONS

- MOVE THE WENDY HOUSE AND PREPARE THE SITE **13m<sup>2</sup>** FOR THE CONSTRUCTION OF THE COCRETE SLAB.
- **EARTHWORKS**
- EXCAVATION IN PICKABLE MATERIAL FOR FOUNDATION TRENCHES N.E 2m DEEP AND AET ASIDE FOR FUTURE USE 11.82m x 0.60m x 0.60m = **4.26m<sup>3</sup>**
- **BACKFILING** IN LAYERS OF 150mm WELL WATERED AND COMPACTED TO 95% MODAASHTO: **5m<sup>3</sup>**
- **CONCRETE WORKS:** 25MPA CONCRETE IN FOUNDATION WITH 19mm STONE: **1.5m<sup>3</sup>**
- **BRICKWORK IN FOUNDATION:** 1 BRICK WALL IN STRETCHER BOND IN STOCK COMMONS IN 1:2 c/m. 11.82m x 0.4m = **5m<sup>2</sup>**
- **half brick wall** in lining with concrete surface bed: **11.82m**
- 100mm **hardcore** material with comprising of broken bricks / or stones: **12.08m<sup>2</sup>**
- 50mm **SAND BLINDING** TO RECEIVE DPM: **12.8m<sup>2</sup>**
- DAMP PROOF MEMBRANE: **12.80m<sup>2</sup>**
- **BRC MERSH REF 193** WITH COVER BLOCKS OR SPACERS: **12.80m<sup>2</sup>**
- 25MPA **REINFORCED CONCRETE** WITH 19MM STONE TO FORM 100mm thick CONCRETE SLAB: **1.21m<sup>3</sup>**
- **RHINOBOARD CEILING BOARD** ON THE SOFITS AND WALLS, SKIMM THE JOINTS AND PAINT THE CEILING BOARD: **32m<sup>2</sup>**